SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-16-94

E. Reed, Co. Rep

BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE

APR 26 1995
COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

12-28-1994 15:07:42

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00002 Page 0336

Register of Deeds Stamp & File Number

For corners in

Branch
OVID TOWNSHIP

Located In: Corner Code #

1. Public Land Survey T 7 S R 6 W E-13
   T ___ R ___
   T ___ R ___
   T ___ R ___
2. Property Controlling S ___ T ___ R ___
   in Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
   Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, Edward W. Reed, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 32, 33, Ovid Township, and Sections 4 and 5, Kinderhook Township, Town 7 South, Range 6 West, Branch County, Michigan.
1825: Brookfield, corner set
1892: Hamilton, corner used
1909: Cox, found stone well planted surrounded with broken tile

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pointed stone and one piece of brick, put railroad spike along stone
Placed 1/2" x 9" rebar iron, remonumentation cap on top of stone
Set cast iron box 2" below grade of gravel road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1/2" rebar as noted:

S 30 W 71.95'	6" square concrete post
S 45 E 52.30'	nail and washer up 2' North side of 6" walnut
S 70 W 53.70'	nail and washer up 2' North side 14" walnut
N 55 E 47.00'	nail and washer up 2' South side of 4" twin maple

STATE OF MICHIGAN
EDWARD W. REED
LAND SURVEYOR
NO. 33985
LICENSED LAND SURVEYOR

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date December 12, 1994

Surveyor's Michigan License No. 33985
EDWARD W. REED

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN., 19