

1993

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

BRANCH (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7</u> S R <u>6</u> W	<u>G - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

273

REGISTER OF DEEDS  
*John J. Morrison*

93 DEC 27 AM 10:07

REC'D FOR RECORD  
STATE OF MICHIGAN  
BRANCH COUNTY

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, EDWARD R. REED, in a field survey on NOVEMBER 04, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

OVID TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:

- Nov., 1825. W. Brookfield, GLO Dep. Surveyor: "80.00 Set post cor secs 9, 10, 15 & 16 Sugar 24 S42½E 34 Beech 10 N56½E 21"
- 8/15/1877. M. Knowles, County Surveyor: "Fd roots of one US bearing tree & stake hole to correspond. Set stone 24" brick below & arround & 2 stones at US tree. Red Oak 30 N72½ S Oak 14 S7E 42½". 2/64-Survey Records.
- April, 1911. J. J. Cox, County Surveyor: "Fd stone (white) in brick. Maple 9 SE 63½ lks, Oak fe post, N 42½ lks, Oak fe post, S 44½ lks". 3/282-Survey Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Continued:

- June, 1957. E. R. Reed, County Surveyor: "Fd. pointed stone 22" deep & brick. Set I. Pipe flush with blacktop. Steel cor post, N 27.66'; RR-tie cor post, S 29.3'; 24" Maple, S40E 41.48'; 11" Maple, S20E 34.82'."
- 4/25/1963. R. Roon, MSHD: "Fd 3/4" pipe near surface of blacktop. RR tie fe post, S 29.76'; 42" Maple, S47E 42.43'; 4" I. Pipe, North 27.65'."


Found I. pipe as noted above. Removed pipe and set ½"x18" rebar iron rod with I.D. cap #7437, over stone, in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

½"x18" rebar iron rod with I.D. cap #7437, over stone, in monument box.:  
 4" dia. steel corner post, North 27.66'; RR-tie corner post, South 29.3' to north face; 38" Maple, S 40 E 42.1' to center; 20" Maple, S 20 E 34.82' to center; 12" Maple, S 08 E 34.2' to center; 36" W. Cherry, N 70 E 84.3' to center; 4.0' north of C/L road.

This is accepted as the careful and faithful perpetuation of the position of the original corner.

Signed by *Edward R. Reed*  
 Surveyor's Michigan License No. 7437



Date 11/04/93