

SECTION

BRANCH COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

11-08-1999 15:15:04

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber 00004 Page 0034

Register of Deeds Stamp & File Number

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
OID TWP		
1. Public Land Survey	T <u>7</u> S <u>R</u> 6 W	<u>H-07</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on SEPTEMBER 5, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 15 & 22

A. Description of original monument and accessories and/or subsequent restoration:

1825: WM BROOKFIELD- CORNER SET  
----- : CARY- FOUND STAKES STANDING, PLANTED STONE & COBBLES  
1894: I.D. MINER - FOUND STONE - SET GRANITE BOULDER 18" LONG, POINT UP  
1963: R. ROON, M.S.H.D. - FOUND LARGE STONE WITH HOLE IN TOP, WITNESSED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE STONE FITTING WITNESS OF M.S.H.D.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" IRON UNDER STONE, SET 1/2" X 18" IRON WITH REMON CAP AT ANGLE OVER STONE, PLACED CARSONITE MARKER ON WEST SIDE OF STONE.

EAST 23.57' NW COR. CONC. ANCHOR POST AT GROUND LEVEL  
WEST 26.75' 14" TWIN OAK  
N40E 33.58' 14" SYCAMORE  
S20W 49.1' 14" SYCAMORE  
IN WEST SIDE OF FARM LANE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

EDWARD W. REED

Surveyor's Michigan License No. 33985

Date OCTOBER 5, 1999

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-06-1999

E. R. Reed, Co. Rep.  
E. R. REED

