

**SURVEY &
MONUMENTATION**

JAN 23 1996

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

Liber **00003** Page **0036**
STATE OF MICHIGAN

BRANCH _____ (County)	Located In:	Corner Code #
OVID TWP.	T <u>7</u> S R <u>6</u> W	H-9
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Branch County
Recorded
09-28-1995 10:21:57
Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward W. Reed, in a field survey on August 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- QUARTER CORNER COMMON TO SECTIONS 22 & 27, T7S, R6W, OVID TWP., BRANCH COUNTY, MI.
1825: Wm. Brookfield, GLO Dep. Surveyor, corner set
1921: E. L. Miner, County Surveyor, found iron stake well preserved
1963: Russell Roon, Survey Chief, M.S.H.D.-found 3/4" pipe
1981: E. R. Reed, County Surveyor, found iron pipe in monument box, recorded L.C.R.C. #II 0036

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid iron, could not remove
Placed cap along side of iron

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
9-13-95
E. R. Reed, Co. Rep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- S35°E 79.0'-NW corner of house
S48°W 54.6'-telephone pedestal
N54°W 58.71'-to 20" walnut tree
N 35.1'-to face of square wood anchor post
N55°E 80.0'-to face of telephone pole

And is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by Edward W. Reed
Surveyor's Michigan License No. 33985

Date August 22, 1995