

BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
BRANCH

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	7S	R	6W	I-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

REGISTER OF DEEDS  
*John J. Morrison*

91 MAR 10 AM 9:48

REC'D FOR RECORD  
STATE OF MICHIGAN  
BRANCH COUNTY

II 287

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EDWARD W. REED, in a field survey on JANUARY 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

QUARTER SECTION CORNER SECTION 10 - 11, T7S, R6W, OVID TOWNSHIP

GLO NOTES: North 40.00, set quarter section post

OLD SECTION CORNER FILE: stone

1948 - HAROLD RUSSELL, County Surveyor: shows iron at quarter section corner for survey in SE 1/4, Section 10.

1977 - RUSSELL ROON, Survey chief, M.S.H.D.: Found gear shaft 5/8" with gear on top, set monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 5/8" iron with gear top in monument box.

Set 1/2" iron over top of old iron with "BRANCH COUNTY REMONUMENTATION MARKER" on top.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CAPPED REBAR IRON "#33985" IN CI-MONUMENT BOX

- OLD WITNESS: Power pole, S 85 E 67.95'
- 38" Maple, N 77 W 33.79'
- NEW WITNESS: 24" Maple, N 44 E 59.3'
- SW corner metal barn, N 71 E 105.4'
- Power Pole, S 50 W 51.6'
- 3" Pine, N 24 W 33.79'



And is accepted at a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed  
Surveyor's Michigan License No. 33985

Date: JANUARY 26, 1994