

# SURVEY & REMONUMENTATION

APR 26 1995

BRANCH COUNTY REMONUMENTATION CORNER

LAND COMMISSION  
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 AT A MEETING HELD ON 12-16-94

E.R. Reed, Co. Rep.

For corners in

<u>BRANCH</u> <small>(County)</small>	Located In:	Corner Code =/
<u>OID TOWNSHIP</u>		
1. Public Land Survey	T <u>7</u> S R <u>6</u> W	<u>J-3</u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
2. Property Controlling in Section	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
3. Miscellaneous Property in Sec.	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
Branch Counts  
Recorded

12-28-1994 15:08:07

Linda Lee Morrison-Matthews  
REGISTER OF DEEDS

Libar 00002 Page 0339  
Register of Deeds Stamp & File Number

I, EDWARD R. REED, in a field survey on NOVEMBER 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

OID TWP., T7S, R6W

A. Description of original monument and accessories and/or subsequent restoration:

**J-3: SOUTH 1/4 CORNER OF SECTION 2, OID TWP., T7S, R6W.**

- G.L.O. FIELDNOTES, W. BROOKFIELD, 1825: "WEST CORRECT BETWEEN SECS 2 & 11. 40.04 SET QTR SEC POST AT AVERAGE DIST. BEECH 10 S70½E 27, BEECH 12 S34½W 26."
- OLD SECTION CORNER FILE CARD = "IRON".
- J. H. BENNETT, DEP. CO. SURVEYOR, 1/52, SURVEYS, 1869: "PLANTED STAKE BOTH U S BEARING TREES STANDING FINELY PRESERVED".
- I. D. MINER, COUNTY SURVEYOR, 3/21, SURVEYS, 1892: "H. QR. POST BETWEEN SECS 2 & 11. FOUND FIRE CLAY WELL TUBING".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. CONTINUED:

E. R. REED, CO. SURVEYOR, 1987: "COR. REFERENCE= IRON & STONES. FD.PLOW SHEAR & ½" IRON. 14" WALNUT S03W 25.6'; 28" MAPLE, S44E 45.5'; 28" TWIN WALNUT S41W 33.3'; 14" WALNUT N47W 31.4'; WOOD ANCHOR POST, N06E 29.3'; 12" WALNUT S64W 57.5'".

B. ALL G.L.O. ORIGINAL WITNESSES ARE GONE.

FOUND IRON STAKE, PREVIOUSLY FOUND BY MYSELF IN 1987, FROM WITNESSES AND ACCEPTED THIS AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
AND SET 1/2" STEEL REBAR ROD, WITH BRANCH COUNTY REMONUMENTATION CAP, IN C-I MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**1/2" STEEL REBAR ROD, WITH BRANCH COUNTY REMONUMENTATION CAP, IN C-I MONUMENT BOX.**


S 03 W 25.60'	CENTER 16" WALNUT	S 44 E 45.51'	CENTER 32" MAPLE
N 47 W 31.40'	CENTER 16" WALNUT	S 64 W 57.50'	CENTER 15" WALNUT
N 06 E 29.30'	FACE OF WOOD ANCHOR POST		
S 12 W 19.52'	CENTER 12" WALNUT		
S 03 W 19.80'	1½" PIPE @ GROUND LEVEL.		

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward R. Reed

Surveyor's Michigan License No. 7437

EDWARD R. REED



Date NOVEMBER 18, 1994