

# SURVEY & REMONUMENTATION

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1999 AT A MEETING HELD ON 12-16-94

E.R. Reed, Co. Rep.

APR 26 1995  
BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION  
Filing Requirements Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

For corners in

12-28-1994 15:08:31

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Liber **000002** Page **0342**  
Register of Deeds Stamp & File Number

Branch _____ <small>(County)</small>	Located In:	Corner Code =#
1. Public Land Survey	T <u>7</u> S R <u>6</u> W	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in-Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Edward W. Reed, in a field survey on September 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Quarter corner common to Section 36, Ovid Township and Section 1, Kinderhook Township, Town 7 South, Range 6 West, Branch County, Michigan  
 1825: GLO Brookfield, set 1/4 post at 40 chains  
 1889: Hamilton, County Surveyor found nothing reset  
 1975: E. R. Reed-County Surveyor recorded #129 (1/16/75), found wagon bolt, and reset 3/4" iron  
 1975: Boone, surveyor, found 3/4" iron, recorded #136 (3/24/75)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3/4" iron 1.8' below new road surface-2-4" mats  
 0.8 fill and 1 old road surface  
 Placed 1/2" x 18" rebar over top of old iron  
 Set cast iron monumentation box flush with road surface



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1/2" rebar as noted above:  
 East-in line with fence  
 West-4.4' North of old fence  
 West 34.07'-nail in North side of old wood post  
 East 28.64'-nail in South side of square wood corner post  
 In centerline of North-South roads

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date September 28, 1994  
 Surveyor's Michigan License No. 33985