

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

STATE OF MICHIGAN
Branch County
Recorded

09-26-2000 10:16:02

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BETHEL TWP		
1. Public Land Survey	T <u>7 S</u> R <u>7 W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

Liber **00004** Page **0094**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Aug 9, 2000
E.R. Reed
E.R. REED, Co. Rep.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 6, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 7, 8, 17 & 18, BETHEL TWP.

A. Description of original monument and accessories and/or subsequent restoration:

1826: WM. BROOKFIELD, CORNER SET
1961: E.R. REED, RESET CORNER FROM EXISTING FENCELINE & SET BOLT & TIED SURVEY TO CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

BOLT AS DESCRIBED BY E.R. REED IN 1961, NOW GONE, RESET POINT FROM OLD SURVEYS TIED TO CORNER SET 1/2" X 18" IRON REBAR WITH REMON CAP IN CAST IRON REMONUMENTATION BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" IRON REBAR WITH REMON CAP IN CAST IRON REMONUMENTATION BOX

TAG IN EAST SIDE OF POWER POLE	S51W	42.16'
TAG IN EAST SIDE OF POWER POLE	N6W	152.10'
TAG IN WEST SIDE OF POWER POLE	N17E	156.20'
TELEPHONE PEDESTAL	N78E	104.31'
TELEPHONE PEDESTAL	S55E	57.33'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED



DATED: JULY 6, 2000

Surveyor's Michigan License No. 33985

