

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE Branch County
Filing Requirement of Act 74, Mich. P.A. 1970 Recorded**

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
BETHEL TWP.		
1. Public Land Survey	T <u>7</u> S R <u>7</u> W	<u>E-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10-22-1997 09:53:37

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0139**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
NORTHEAST CORNER SECTION 5, NORTHWEST CORNER SECTION 4,
BETHEL TWP

- 1826: W. BROOKFIELD, DEPT. SURVEYOR - CORNER SET
- 1941: H. RUSSELL, CO. SURVEYOR - FOUND IRON ROD
- 1977: E.R. REED, CO. SURVEYOR - FOUND 3/4" IRON ROD WITH ADDITIONAL PIECE OF IRON AND BROKEN STONEWARE ALONG SIDE, RECORDED IN LCRC # 0197

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD AS DESCRIBED IN LCRC # 0197

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD GRADE

- 22" WALNUT, N22W 106.7' TO CENTER
- 24" MAPLE, S53E 34.8' TO CENTER
- TEL. PED, S40W 45.1' TO FACE
- MAPLE CLUMP, S80W 26.3'
- 57.5' SOUTH OF C/L OF US-12

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97

E.R. Reed, P.S. Co. Rep.
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed
EDWARD W. REED

Date JUNE 10, 1997

Surveyor's Michigan License No. 33985

