

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

BRANCH COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:53:44

For corners in

<u>BRANCH</u> (County)	Located In:	Corner Code #
BETHEL TWP.		
1. Public Land Survey	<u>T 7 S R 7 W</u>	<u>E-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0140**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
QUARTER CORNER COMMON TO SECTIONS 4 & 5

- 1826: W. BROOKFIELD, DEPT. SURVEYOR - CORNER SET
- 1869: J. BENNETT, CO. SURVEYOR - STONE, BRICK AND GLASS
- 1977: E.R. REED, CO. SURVEYOR - FOUND 1 1/4" IRON PIPE WITH LARGE STONE ON SOUTH SIDE, ALL SURROUNDED BY BRICK BATS, RECORDED IN LCRC # 197

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH FLAGGING, ALSO FOUND STONE AND BRICKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 1/2" X18" REBAR IRON WITH REMON CAP IN CI-MONUMENT 4" BELOW GRAVEL ROAD GRADE

- P. POLE N11W 119.8' TO FACE
- TEL. PED, N37W 46.8' TO FACE
- P. POLE, S26W 85.1' TO FACE
- SQUARE WOOD ANCHOR POST, N88E 25.9' TO FACE
- 18" ASH, N29E 62.9' TO CENTER
- IN LINE WITH FENCE RUNNING EAST & WEST

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON


9-10-97
E.R. Reed, P.S. G. Rep.
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date JUNE 10, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985



MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28
REVISED MAY 14, 1975