

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

For corners in

BRANCH (County)	Located in:	Corner Code #
BETHEL TOWNSHIP	T 7 S R 7 W	G-2
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10-22-1997 09:53:57

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0142

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on APRIL 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3							●						
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1826: WM BROOKFIELD, DEPT. SURVEYOR, CORNER SET
1973: DAVID BOONE, SURVEYOR, FOUND STONE DOWN 2 FEET, SET IRON PIN OVER STONE, RECORDED IN LCRC # 063
1991: DONALD ANDREWS, SURVEYOR, FD 5/8" IRON BAR- SET MONUMENT BOX RECORDED IN LCRC # II-191

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97
E.R. Reed, P.S. Co. Rep.
E.R. REED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON BAR IN CI-MONUMENT BOX FITTING WITNESS OF LCRC II-191
SET REMONUMENTATION CAP ON EXISTING IRON

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REMONUMENTATION CAPPED IRON IN CI-MONUMENT BOX
NAIL & CAP IN TEL. POLE, N50E 39.72'
NAIL & CAP IN POWER POLE, S55E 34.77'
"X" TOP OF GTE POST, N40W 38.27'
TOP OF HAND PUMP, S80W 49.40'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed

Date APRIL 26, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985