

**SURVEY & REMONUMENTATION**

**MAR 2 1 1997**

**BRANCH COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN  
Branch County  
Recorded

10-30-1996 09:13:22

Linda Lee Morrison-Matheus  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**COMMISSION**

For corners in

BRANCH (County)	Located In:	Corner Code #
BRONSON TWP.		
1. Public Land Survey	T <u>7S</u> R <u>8 W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **EDWARD W. REED**, in a field survey on **SEPTEMBER 4**, 19 **96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:**
- CORNER COMMON TO SECTIONS 9, 10, 15, & 16, T7S, R8W, BRONSON TWP., BRANCH COUNTY, MI
  - 1826: W. BROOKFIELD, DEP. SURVEYOR, CORNER SET
  - 1879: KNOWLES, COUNTY SURVEYOR, FOUND A STONE, TWO STAKE HOLES & THE BOTTOM OF BOTH US TREES
  - 1884: HAMILTON, FOUND STONE
  - 1897: I.D. MINER, SURVEYOR, FOUND BLUE GRANITE & PLANTED BRICK BENNETT, SURVEY, FOUND STONE LONG USED
  - 1945: H. RUSSELL, COUNTY SURVEYOR, IRON PIPE SET
  - 1994: DONALD ANDREWS, FOUND STONE, RECORDED L.C.R.C.#III-005

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND BROKEN LEAF SPRING 1/2" x 6" IRON & FLAGGING OVER TOP POINTED STONE  
SET CAST IRON BOX WITH REMONUMENTATION CAP OVER TOP OF STONE



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1/2 x 6" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX  
SW 44.03' TO CENTER OF 24" WALNUT  
SSW 90.21' TO CENTER OF 8" WALNUT  
SSW 107.29' TO CENTER OF 36" OAK  
SSW 101.5' TO CENTER OF 5" WALNUT  
N 381.76' TO S EDGE OF S RAILROAD TRACK

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 9, 1996  
*E.R. Reed Co. Rep.*  
**E.R. REED**

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed* Date SEPTEMBER 4, 1996  
Surveyor's Michigan License No. EDWARD W. REED 33985