

SURVEY & REMONUMENTATION

FEB 13 2001

**SECTION BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

09-26-2000 10:16:13

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BRONSON TWP		
1. Public Land Survey	T <u>7</u> S R <u>8</u> W	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

Liber **00004** Page **0095**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Aug 9, 2000

E.R. Reed
E.R. REED, Co. Rep.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on AUGUST 2, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: BROOKFIELD-CORNER SET
OLD NOTES OF COUNTY SURVEYOR INDICATE "STONE"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ALL EVIDENCE OF CORNER GONE DUE ROAD RECONSTRUCTION AND DRAIN
RESET CORNER ON NORTH LINE OF SECTION @GLO OFFSET DISTANCE OF 1.64 CHAINS
SET 1/2" X 18" REBAR IRON OVER 3/4" X 30" REBAR IRON IN CAST IRON BOX 4" BELOW GRAVEL ROAD SHOULDER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON OVER 3/4" X 30" REBAR IRON IN CAST IRON BOX		
CENTERLINE ROAD	WEST	23.07'
SOUTHWEST CORNER OF SECTION		
36, MATTESON TWP.	WEST	1.64 CHAINS
NORTHEAST CORNER OF HOUSE	S62W	114.70'
TELEPHONE POLE	S18E	87.76'
TAG & NAIL NORTH SIDE 60" OAK	S41E	31.90'
TAG & NAIL EAST SIDE POWER POLE	N28W	286.30'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

DATED: AUGUST 2, 2000

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

