

SURVEY & REMONUMENTATION

FEB 13 2001

**BRANCH COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

SECTION

For corners in

<u>BRANCH COUNTY</u> BRONSON TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>7</u> S R <u>8</u> W	<u>K-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___	_____
	T ___ R ___	_____
3. Miscellaneous	S ___	_____
	T ___ R ___	_____
Property in Sec.	S ___	_____
	T ___ R ___	_____

09-26-2000 10:16:28

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00004** Page **0096**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Aug 9, 2000
E.R. Reed
E.R. REED, Co-Rep.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on August 1, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 13 & 14, BRONSON TWP.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: W.M.BROOKFIELD-CORNER SET
- 1862: M. KNOWLES-STONE & BRICK
- 1892: I.D. MINER, FOUND IRON AND PLANED GRAY GRANITE BOULDER ABOVE IT
- 1952: H.L. RUSSELL-SURVEY TIED TO CORNER
- E.R. REED, FOUND IRON STONE ABOVE IT, SET 3/4 X 20 IRON BAR WITH WITNESS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ALL OLD WITNESS NOW GONE, FOUND 3/4" IRON ROD EXACTLY ON SPLIT BETWEEN NORTHWEST CORNER & SOUTHWEST CORNER,
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT-BOX FLUSH WITH PAVED ROAD SURFACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NAIL 2' UP IN 36" OAK	S27W	106.79'
NAIL 2' UP IN P. POLE	S83W	30.32'
NAIL 2' UP IN 24" CATALPA	N26W	102.01
NAIL 3' UP IN P. POLE	N24E	78.35'
CENTERLINE OF ORLAND RD	EAST	1.5'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

Date AUGUST 7, 2000

EDWARD W. REED

Surveyor's Michigan License No. 33985

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

