

**SURVEY & REMONUMENTATION**

FEB 08 1999

**SECTION**

**BRANCH COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                          |                          |               |
|------------------------------------------|--------------------------|---------------|
| <u>BRANCH COUNTY</u><br>BRONSON TOWNSHIP | Located In:              | Corner Code # |
| 1. Public Land Survey                    | T <u>73</u> R <u>8 W</u> | <u>K-13</u>   |
|                                          | T ___ R ___              | _____         |
|                                          | T ___ R ___              | _____         |
|                                          | T ___ R ___              | _____         |
| 2. Property Controlling<br>in Section    | S ___ T ___ R ___        | _____         |
|                                          | S ___ T ___ R ___        | _____         |
| 3. Miscellaneous<br>Property in Sec.     | S ___ T ___ R ___        | _____         |
|                                          | S ___ T ___ R ___        | _____         |

STATE OF MICHIGAN  
Branch County  
Recorded

11-04-1998 15:48:31

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JULY 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO NOBLE TOWNSHIP, SECTIONS 1 AND 2 AND BRONSON TOWNSHIP, SECTIONS 35 AND 36

A. Description of original monument and accessories and/or subsequent restoration:

1825: JOHN MULLETT, D.S. - CORNER SET  
1881: SURVEY BY C. HAMILTON, COUNTY SURVEYOR - STAKE  
1882: SURVEY BY C. HAMILTON, COUNTY SURVEYOR - NO EVIDENCE OF CORNER, RE-ESTABLISHED CORNER, PUT LONG STAKE WITH PLOW POINT  
OLD SECTION CORNER INDICATES 1" IRON PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE BELOW ROAD SURFACE  
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


1/2" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX

POWER POLE S 70 E 102.4' TO FACE  
TEL PED S 40 E 49.1' TO FACE  
POWER POLE S 23 W 116.4' TO FACE  
TEL PED S 55 W 43.0'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-07-1998

*E.R. Reed Co. Rep.*  
**E.R. REED**



Liber 00003 Page 0231

Signed by *Edward W. Reed*

EDWARD W, REED

Date SEPTEMBER 9, 1998

Surveyor's Michigan License No. 33985