

34860

SURVEY & MONUMENTATION

DEC 28 2000

BRANCH COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
Branch County  
Recorded

09-29-1999 11:58:52

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

*Seg. 2*

Register of Deeds Stamp & File Number

*Minion A. Brown 200*

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
BRONSON TWP		
1. Public Land Survey	T <u>7</u> S R <u>8</u> W	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on AUGUST 5, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO BRONSON TOWNSHIP, SECTION 35 AND 36 AND NOBLE TOWNSHIP, SECTIONS 1 AND 2

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GLO FIELD NOES OF JOHN MULLETT, D.S.
- 1881: SURVEY BY C. HAMILTON, COUNTY SURVEYOR
- 1882: SURVEY BY C. HAMILTON, COUNTY SURVEYOR
- 1916: SURVEY BY D. W. DUDLEY, DEP. COUNTY SURVEYOR
- OLD SECTION CORNER FILE CARD FOR BRONSON TOWNSHIP, (COMMON CORNER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MONUMENT BOX  
SET REMONUMENTATION CAP ON IRON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" IRON WITH REMONUMENTATION CAP IN CAST IRON MONUMENT BOX

- TELEPHONE POLE (FACE OF) S 50 E 52.2'
- TELEPHONE PEDESTAL (FACE OF) S 41 W 44.1'
- POWER POLE (FACE OF) S 73 W 80.5'
- 36" MAPLE (CENTER OF) N 33 E 60.2'

AND IS ACCEPTED AS A CAREFULLY AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

EDWARD W, REED

Date SEPTEMBER 9, 1998

Liber 00004 Page 0010

Surveyor's Michigan License No. 33985

THIS IS A RE-RECORDING OF LCRC RECORDED NOV. 4, 1999, IN LIBER 00003, PAGE 0233, BRANCH COUNTY REGISTER'S OFFICE.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-09-1998

*E. R. Reed, Co. Rep.*

