

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH _____	Located In:	Corner Code #
(County)		
CALIFORNIA TWP.		
1. Public Land Survey	T <u>8</u> S R <u>5</u> W	G-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

10-22-1997 09:54:25

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0146**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 3-4 CALIFORNIA & 33-34 ALGANSEE

- 1825: JOHN MULLET, DEPT. SURVEYOR - CORNER SET
- 1877: M. KNOWLES, CO SURVEYOR - FOUND STONE
- 1989: E.R. REED, CO SURVEYOR - FOUND 1" SQUARE SHAPED IRON NEAR CENTER OF ROAD INTERSECTION ABOUT 10" DEEP, RECORDED IN LCRC # II-133

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SQUARE IRON BAR AS RECORDED IN LCRC # II-133
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" REBAR IRON, REMON CAP IN CI-MONUMENT BOX

- C/L S. END N-S CMP ROAD CULVERT, S32E 36.7'
- C/L N. END N-S CMP ROAD CULVERT, N35E 37.1'
- C/L W. END E-W CMP ROAD CULVERT, N06W 112.9'
- TEL. PEDESTAL, S37W 58.1' TO FACE


ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-10-97
E.R. Reed, P.S. Co. Rep.
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date JUNE 20, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28
REVISED MAY 14, 1975

REVISED JAN., 198
REVISED OCT., 199