

FEB 08 1999

BRANCH COUNTY REMONUMATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Liber 000003 Page 0267
 STATE OF MICHIGAN
 Branch County
 Recorded

12-07-1998 13:56:32

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>BRANCH COUNTY</u> CALIFORNIA TWP	Located In:	Corner Code #
1. Public Land Survey	<u>T 8 S R 5 W</u>	<u>G-06</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-04-1998

E.R. Reed Co. Rep.
E.R. REED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 30, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 15 & 16

A. Description of original monument and accessories and/or subsequent restoration:

1828: ROBERT CLARK, JR. DEPT SURVEYOR - CORNER SET
 OLD NOTES OF E.R. REED, SURVEYOR - STONE & BRICK WITH WITNESS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FROM OLD WITNESS, DUG LARGE HOLE, FOUND STONE & BRICK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE, SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

WITNESS TAG IN W. SIDE 38" OAK	S 12 E	96.33'
WITNESS TAG IN W. SIDE RR TIE CORNER POST	S 46 E	46.78'
SW CORNER TEL PED	N 36 E	47.70'
SW CORNER HOUSE	N 41 E	130.18'
WITNESS TAG E. SIDE OF 26" MAPLE	N 10 W	134.13'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Edward W. Reed*
 EDWARD W, REED

Date NOV. 4, 1998

Surveyor's Michigan License No. 33985

