

SURVEY &
MONUMENTATION

JAN 23 1996 BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00003 Page 0033

For corners in

BRANCH (County)	Located In:	Corner Code #
KINDERHOOK TWP		
1. Public Land Survey	T 8S R 6W	F-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

09-28-1995 10:21:31

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Edward W. Reed, in a field survey on June 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- QUARTER CORNER COMMON TO SECTIONS 4 & 9, T8S, R6W, KINDERHOOK TWP., BRANCH COUNTY, MI.
 1828: Robert Clark, Jr., Deputy Surveyor, -set corner
 1902: Chas. Hamilton, County Surveyor, -stone and brick
 1909: J. J. Cox-stone in brick
 1953: E. R. Reed, County Surveyor, -survey tied to corner, found stone
 1965: E. R. Reed-found stone and set iron over stone
 1976: E. R. Reed, County Surveyor, L.C.R.C.#180 recorded
 1989: E. W. Reed-survey tied to corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1/2" iron on top of stone
 Set monument box flush with road surface
 Set remonumentation cap over iron

ACCEPTED BY THE BRANCH COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
9-13-95

E. R. Reed, Co. Rep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- N25°W 36.3'-to 24" maple tree
 N48°E 39.1'-to telephone pedestal
 N62°E 40.2'-to power pole
 S59°E 45.6'-to power pole
 S25°E. 33.5'-to 18" hickory tree
 N01°E 33.3'-to steel post remains in concrete
 In centerline of E-W road



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Edward W. Reed Date June 19, 1995
 Surveyor's Michigan License No. 33985