

SURVEY & REMONUMENTATION

MAR 21 1997

BRANCH COUNTY REMONUMENTATION CORNER STATE OF MICHIGAN
LAND CORNER RECORDATION CERTIFICATE Branch County
Recorded
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

10-30-1996 09:20:48

BRANCH <small>(County)</small>	Located In:	Corner Code #
KINDERHOOK TWP.		
1. Public Land Survey	T <u>8</u> S R <u>6</u> W	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber **00003** Page **0081**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward W. Reed, in a field survey on AUGUST 12, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- CORNER COMMON TO SECTIONS 3, 4, 9 & 10, T8S, R6W, KINDERHOOK TWP., BRANCH COUNTY, MI
- 1828: R. CLARK, JR., DEP. SURVEYOR, CORNER SET
 - 1909: J.J. COX, SURVEYOR, FOUND STONE WITH CROSS
 - 1960: E.R. REED, COUNTY SURVEYOR, USED CORNER
 - 1963: D. HOTH, M.S.H.D. SURVEY CHIEF, FOUND PIPE
 - 1973: GOVE ASSOC. INC., FOUND 1" PIPE
 - 1977: WAYNE MOST, FOUND CORNER, RECORDED AS SE CORNER SECTION 3, BUT SURVEYED AS SE CORNER OF SECTION 4
 - 1983: F.J. CUTCHER, SURVEYOR, FOUND 1" PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1" PIPE IN CAST IRON BOX
REMOVED PIPE AND SET 1/2" x 12" REBAR AND REMONUMENTATION CAP

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 9, 1996

E.R. Reed, Co. Rep.
E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" x 12" REBAR WITH REMONUMENTATION CAP IN CAST IRON BOX
- N10E 26.81' TO FACE OF TELEPHONE POLE
- N70W 139.7' TO FACE OF POWER POLE
- N24W 117.4' TO SW CORNER OF HOUSE ADDITION
- N85E 181.3' TO FACE OF POWER POLE
- N65W 105.3' TO CENTER OF 36" WALNUT
- N12E 32.0' TO CENTER OF 18" WALNUT



And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *Edward W. Reed* Date AUGUST 12, 1996
Edward W. Reed
Surveyor's Michigan License No. 33985