

**SURVEY &
REMONUMENTATION**

MAR 21 1997

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

00003 Page 0084

STATE OF MICHIGAN

Branch County

Recorded

10-30-1996 09:21:58

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in **COMMISSION**

BRANCH (County)	Located In:	Corner Code #
KINDERHOOK TWP. 1. Public Land Survey	T 8 S R 6 W	J-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, EDWARD W. REED, in a field survey on SEPTEMBER 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 QUARTER CORNER COMMON TO SECTIONS 2 & 11, T8S, R6W, KINDERHOOK TWP., BRANCH COUNTY, MI
 1828: R. CLARK, JR., DEP. SURVEYOR, CORNER SET
 1978: E.R. REED, COUNTY SURVEYOR, FOUND 1 1/2" WELL POINT WELL SET IN STONES, 17" BELOW ROAD SURFACE, TO TOP OF WELL POINT. SET A 1/2" x 18" IRON ROD OVER WELL POINT AND PLACED A CAST IRON MONUMENT BOX OVER SAME

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" IRON IN MONUMENT BOX AS DESCRIBED IN L.C.R.C.#237
 PLACED REMONUMENTATION CAP ON IRON
 RAISED BOX TO ROAD SURFACE WITH RINGS



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1/2" x 18" IRON WITH REMONUMENTATION CAP IN CAST IRON BOX
 N 29.9' TO FACE OF SQUARE WOOD ANCHOR POST
 S 30.5' TO FACE OF 4" DIAMETER STEEL ANCHOR POST
 S33W 30.3' TO FACE OF TELEPHONE POLE
 S50W 40.5' TO CENTER OF 44" MAPLE
 IN LINE WITH FENCELINE N-S

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Oct. 9, 1996.
E. R. Reed Co. Rep.
E.R. REED

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed Date SEPTEMBER 17, 1996
 EDWARD W. REED
 Surveyor's Michigan License No. 33985