

SECTION

BRANCH COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE STATE OF MICHIGAN
Branch County
Recorded

For corners in

<u>KINDERHOOK TWP.</u> (County) BRANCH COUNTY	Located In:	Corner Code #
1. Public Land Survey	T 8 S R 6 W	K - 07
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

11-08-1999 15:15:22

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00004 Page 0036
Register of Deeds Stamp & File Number

I, Edward R. Reed, in a field survey on August 9, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

KINDERHOOK TWP.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 K-07: SECTION CORNER COMMON TO SECTIONS 13, 14, 23 & 24, KINDERHOOK TWP.
 G.L.O. - Robert Clark, Jr., D.S., 1828. Set Stake.
 M. Knowles, Co. Surveyor, 1877: "Fd. stone."
 C.B. Wood, RLS, 1963(?). Iron pipe fd. or set by Wood.
 E.R. Reed, Co. Surveyor, 1987: Fd. iron pipe in stones (2' deep). Steel post West 26.8' 16" Oak, N60E 28'; Fenceline E & W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 From my witnesses of 1987, Fd. top of I. pipe down 6" and stones down 22".
 Drove I. pipe down and set 1/2" x 18" rebar with Branch County Remonumentation Cap on rebar, in I. pipe. All set in CI monument box, below road grade.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Branch County Remonumentation Cap, on rebar, in I. Pipe, in CI monument box:

- West 26.75' - E. Edge of L-Iron anchor post.
- N60E 27.67' - Nail & spotter, W. side 30" Oak.
- S75E 26.38' - Nail & flagging, west side of RR-tie anchor post.
- East 91.70' - West face of powerpole. (Powerline N & S)
- Approx. 3.5' East of C/L gravel road.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1930 AT A MEETING HELD ON OCT. 2, 1999
E. Reed, Co. Rep.
 E.R. REED



Signed by *Edward R. Reed* Edward R. Reed, P.S. Date August 9, 1999

Surveyor's Michigan License No. 7437