

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

BRANCH COUNTY REMONUMENTATION CORNER 00003 Page 0113
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BRANCH _____ (County)	Located In:	Corner Code #
GILEAD	T 8 S R 7 W	B-1
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 Branch County
 Recorded

12-30-1996 14:12:15

Linda Lee Morrison-Mathews
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, EDWARD W. REED, in a field survey on NOVEMBER 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- NORTH QUARTER CORNER OF SECTION 6, T8S, R7W, GILEAD TWP. BRANCH COUNTY, MI.
- 1825: JOHN MULLETT, DEP. SURVEYOR, CORNER SET
- 1868: A.R. DAY, DEP. COUNTY SURVEYOR, "QUARTER POST"
- 1870: J.H. BENNETT, DEP. COUNTY SURVEYOR, "FOUND STUMP ONE W.S. BEARING AND CAST SLEIGH SHOE WELL PLANTED"
- 1986: E.R. REED, COUNTY SURVEYOR, "IRON NOW GONE-RESET CORNER FROM EXISTING CONCRETE POST, 33' EAST OF CORNER" SET 3/4"x18" IRON ROD, RECORDED L.C.R.C. #II-089

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4"x18" IRON ROD
 SET REMONUMENTATION CAP ON IRON AND SET MONUMENT BOX FLUSH WITH ROAD SURFACE.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON NOV. 13, 1996

E.R. Reed, Co. Rep.
 E.R. REED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x18" IRON ROD WITH REMONUMENTATION CAP IN CAST IRON BOX
 N45E 35.3' TO CENTER OF 30" SQUARE CONCRETE POST
 N70W 148.6' TO FACE OF POWER TRANSFER POLE
 S10E 22.6' TO CMP DRIVEWAY CULVERT
 S75E 117.30' TO FACE OF POWER POLE
 S45W 35.6' TO FACE OF TELEPHONE PEDESTAL
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed Date NOVEMBER 8, 1996
 Surveyor's Michigan License No. 33985