

SURVEY & MONUMENTATION

JAN 23 1996

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BRANCH _____
(County)

COMMISSION

Located In:

Corner Code #

GILEAD TWP

1. Public Land Survey

T 8 S R 7 W C-3

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
Branch County
Recorded

09-28-1995 10:20:00

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Liber 00003 Page 0021

Register of Deeds Stamp & File Number

Edward W. Reed in a field survey on June 16, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER COMMON TO SECTIONS 5, 6, 7, & 8, T8S, R7W, GILEAD TWP., BRANCH COUNTY, MI.

1828: Robert Clark, Jr., GLO Dept, Surveyor-set corner

1893: Hamilton, Dep. County Surveyor, found corner well preserved, iron, axle, & cobbles

1948: H. L. Russell, County Surveyor, found corner

1976: D. Boone, corner used in survey

1981: E. R. Reed, County Surveyor, found 1/2" x 18" iron over old iron 36" deep.

Rebar set by Boone. Recorded L.C.R.C. II-0048

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" iron rebar

Set monument box and remonumentation cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

N85°W 36.7'-12" walnut

S28°W 108.2'-to center of 36" walnut

N 20°W 87.2'-to center of 24" walnut

N48°E 48.0'-to nail and spotter on top of wood anchor post

Located 2.6" E of centerline of N/S road and 2.3" S of center of Hoopengartner Road.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

7-13-95

E.R. Reed, Co. Rep.

Signed by Edward W. Reed

Date June 16, 1995

Surveyor's Michigan License No. 33985

