

**SURVEY & REMONUMENTATION**

FEB 06 1999

**SECTION**

**BRANCH COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BRANCH</u>	Located In:	Corner Code #
(County)		
<u>GILEAD TWP.</u>		
1. Public Land Survey	T <u>8</u> S R <u>7</u> W	<u>G - 05</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
In Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN

Branch County

Recorded

11-04-1998 15:49:28

Linda Lee Morrison-Mathews  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**GILEAD TOWNSHIP**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward R. Reed, P.S. in a field survey on JUNE 01, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
CORNER COMMON TO SECTIONS 9, 10, 15 & 16, GILEAD TWP., T8S, R7W.

1828: G.L.O. ROBT. CLARK, JR. D.S.: "SET POST COR. SECS 9, 10, 15, 16. OAK 14 N83½E 100, B OAK 15 S87W 105".

UNKNOWN SURVEY INFORMATION IN SECTION CORNER FILE: "STONE, ON END, 16" DEEP: STEEL ANCHOR POST N45E 37.1', STEEL ANCHOR POST N45W 33.0'."

1984: L. GERSCHBACHER, RLS#18990: "FD.3" SQ. STONE OF RECORD 16"-18" BELOW ROAD SURFACE. REPLACED WITH 5/8"X24" RE-BAR & RLS CAP. (LEFT STONE IN BOTTOM OF HOLE)"  
RECORDED L.C.R.C. # 2/072.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FROM WITNESSES OF L.C.R.C. 2/072 BY GERSCHBACHER, I FOUND THE 5/8" REBAR WITH RLS CAP ON TOP, IN BLACKTOP PAVEMENT.  
I REMOVED THE 5/8" REBAR AND SET A 1/2"X18" REBAR WITH A BRANCH COUNTY REMONUMENTATION CAP AT SAME LOCATION AND PLACED A C-I MONUMENT BOX WITH CONCRETE AROUND THE REBAR.


ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON SEPT. 9, 1998

E.R. Reed Co. Rep.  
E.R. REED

Liber 00003 Page 0239

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" REBAR WITH REMONUMENTATION CAP, IN CONCRETE, IN A C-I MONUMENT BOX.  
N34E 33.80' TO NEAR FACE OF WOOD CORNER POST  
S25E 42.0' TO ROAD NAME SIGN.  
S50W 36.50' TO NE CORNER OF TELEPHONE PEDESTAL (SQUARE).  
S33W 34.90' TO NEAR FACE OF WOOD CORNER POST (ELECTRIC FENCE ATTACHED).  
N45W 33.40' TO CENTER OF HOLE IN TOP OF 5" DIA. STEEL FENCE POST.



Signed by Edward R. Reed  
Date JUNE, 1, 1998  
Surveyor's Michigan License No. EDWARD R. REED, P.S. 07437