

**BRANCH COUNTY REMONUMENTATION PROGRAM**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 Branch County  
 Recorded

**SECTION**

For corners in

<u>BRANCH COUNTY</u> GILEAD TWP	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>7W</u>	<u>I-3</u>
	T____ R____	_____
	T____ R____	_____
	T____ R____	_____
2. Property Controlling in Section	S____ T____ R____	_____
	S____	_____
	T____ R____	_____
3. Miscellaneous	S____	_____
	T____ R____	_____
Property in Sec.	S____	_____
	T____ R____	_____

12-30-1999 11:03:59

Linda Lee Morrison-Mathews  
 REGISTER OF DEEDS

Liber **00004** Page **0072**

Register of Deeds Stamp & File Number

ACCEPTED BY THE BRANCH COUNTY  
 SURVEY PEER GROUP AS THE OFFICIAL  
 CORNER UNDER MICHIGAN PUBLIC ACT 345  
 OF 1990 AT A MEETING HELD ON  
DEC. 07, 1999

*E.R. Reed, P.S.*  
**E. R. REED**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCT. 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

CORNER COMMON TO SECTIONS 2, 3, 10, & 11

A. Description of original monument and accessories and/or subsequent restoration:

1825: WM. BROOKFIELD-CORNER SET  
 OLD SURVEY NOTES INDICATE STONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE 24" DEEP FITTING OLD TREE LINE AND OLD ANCHOR POST @ 24.75'  
 PLACED IRON AROUND STONE  
 SET 1/2" X 18" REBAR IRON (OVER STONE ) WITH REMON CAP IN CAST IRON MONUMENT BOX 5" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 18" REBAR IRON WITH REMON CAP IN CAST IRON MONUMENT BOX  
 N31E 34.17' CORNER OF I-BEAM CORNER POST  
 N16W 63.00' SPIKE EAST SIDE 50" MAPLE  
 N6W 112.62' SPIKE EAST SIDE 50" MAPLE  
 S35E 41.54; NW CORNER TELEPHONE PEDESTAL

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*  
 EDWARD W. REED

Date OCT. 21, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

