

**SURVEY &
REMONUMENTATION**

MAR 13 1998

SECTION

**BRANCH COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
Branch County
Recorded

12-30-1997 10:05:15

Linda Lee Morrison-Matheus
REGISTER OF DEEDS

Liber **00003** Page **0191**

Register of Deeds Stamp & File Number

For corners in

BRANCH	Located In:	Corner Code #
(County)		
GILEAD TWP.		
1. Public Land Survey	T <u>8</u> S <u>R</u> 7 W	<u>1-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on SEPTEMBER 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 14-15-22-23

- 1828: ROBERT CLARK JR, DEPT SURVEYOR - SET CORNER
- : M. KNOWLES, SURVEYOR - FOUND DEPOSIT OF EARTHEN AT DEPTH OF 2 FEET, FOUND NO STONE, SET STONE FOR CORNER
- : H.K. GOTTSCHALK, SURVEYOR - SURVEY TIED TO CORNER, NOTES "FOUND SECTION"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 8" IRON WITH FLAGGING, NO STONE LOCATED UNDER POINT
SET 1/2" X 18" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD GRADE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- CONC. ANCHOR POST, EAST 18.3' TO TOP CENTER
- 18" ASH, N55E 25.3' TO CENTER
- 10" ASH, S19W 69.1' TO CENTER
- ROUND WOOD CORNER POST, S46W 37.2' TO FACE
- TEL. PED, N69W 54.3' TO FACE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date SEPTEMBER 23, 1997

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-08-97

E.R. Reed
E.R. REED

