

SURVEY & REMONUMENTATION

FEB 03 1999

SECTION

**BRANCH COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BRANCH COUNTY</u>	Located In:	Corner Code #
Noble Twp.		
1. Public Land Survey	T <u>8</u> R <u>8</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
Branch County
Recorded

11-04-1998 15:48:58

Linda Lee Morrison-Mathews
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EDWARD W. REED, in a field survey on JULY 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 1,2,11,12

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: R. CLARK, JR., DEPT SURVEYOR; - CORNER SET
- 1882: C. HAMILTON, CO SURVEYOR; - FOUND STONE CORRESPONDING TO STUMP OF ONE WITNESS TREE
- 1909: JOHN COX, CO. SURVEYOR; - FOUND STONE LONG USED
- OLD SURVEY NOTES: IRON ROD OVER STONE & BRICK
- 1993: E.R. REED, CO. SURVEYOR; - IRON ROD

ACCEPTED BY THE BRANCH COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-09-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E.R. Reed, Co Rep.

E.R. REED

FOUND IRON ROD OVER STONE & BRICK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1/2" IRON ROD OVER STONE, PLACED CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

- TEL PED. N 45 W 39.4'
- NW COR. HOUSE S 45 E 95.6'
- TEL. PED S 55 E 51.4' TO NEAR FACE
- POWER POLE N 42 W 62.5' TO FACE
- TEL PED, N 65 E 50.3 TO SW COR.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

Date SEPTEMBER 9, 1998

Liber 00003 Page 0235

Surveyor's Michigan License No. 33985

