

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-- 27 T. 1 S., R. 4 W.		I-9, I-11
2. PROPERTY CONTROLLING IN SECTION-----, T.----- N. S., R.----- E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION-----, T.----- N. S., R.----- E. W.		
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>I-9 Iron post, 30" long, 2-1/2" Diameter, 25" in the ground, encircled with a collar of stone, 2-1/2 feet base to top, with brass cap marked:</p> <p style="text-align: center;">T1S, R4W <u>S22 S23</u> <u>S27 S26</u> 1971</p>	<p>I-11 Iron post, 30" long, 2-1/2" diameter, 25" in the ground, with brass cap marked:</p> <p style="text-align: center;">T1S, R4W <u>S27 S26</u> <u>S34 S35</u> 1971</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-9 & I-11 Found monuments as described above from 1971 field notes of the U.S. Bureau of Land Management dependent resurvey of section boundaries, subdivision of sections, and extension of survey to include omitted lands in Sections 23, 24, 25, 26, 27, and 35, Township 1 South, Range 4 West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>I-9 NE Corner, Section 27 Described above West, 7.50', 48" R. Oak, Spike & Tag S 50° E, 24.21', 20" R. Oak, Spike & Tag In old fence row. South, 6', barbed wire fence.</p>	<p>I-11 SE Corner, Section 27 Described above In marsh - no witnesses available.</p>
---	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 11-19-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655