

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>34</u> T. <u>1</u> S., R. <u>4</u> W.		G-12, I-12
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

<p>G-12 1" Pipe <math>\oslash</math> Gravel Road,  N 40° W, 59.30', 8" Hickory  N 35° E, 63.45', 26" Oak  S 40° E, 46.85', 12" Oak</p>	<p>I-12 E 1/4 Corner, Section 34  Tile and brick (Gifford 1888)  S 71-1/2° W, 45 Lks., 5" Sgr. Maple  S 45-1/4° W, 58 Lks., 5" Sgr. Maple</p>
--	---

Pipe (Witnesses from Davis)  
S 30° W, 71.6', 30" Maple  
S 15° W, 91.4', 24" Maple  
West, 48.9', Iron (Aldens 1/4 Corner)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

<p>G-12 Found 1-1/4" Pipe in <math>\oslash</math> Road.</p>	<p>I-12 Corner was destroyed during relocation of 28 Mile Road. Obtained witness records of Gifford Corner Calhoun County Road Comm. Re-set corner from these witnesses. Found a 1/2" rod that Alden had called the 1/4 corner. Davis stated that the witnesses he had were a perpetuation of Giffords corner. Alden's corner was noted, but not accepted as the 1/4 corner.</p>
---	--

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>G-12 West 1/4 Corner, Section 34  1-1/4" Pipe, 0.6' Below <math>\oslash</math> of road at fence line west.  S 60° W, 40.85', 14" Hickory, Spike &amp; Tag  N 45° W, 47.04', 20" R. Oak, Spike &amp; Tag  N 42° E, 38.52', 15" Hickory, Spike &amp; Tag  S 58° E, 34.22', 24" W. Oak, Spike &amp; Tag</p>	<p>I-12 East 1/4 Corner, Section 34.  Set 3/4" pipe in monument box.  S 23° W, 91.43', 28" Maple, Spike &amp; Tag (Old Wit.)  S 29° W, 71.47', 30" Maple, Spike &amp; Tag (Old Wit.)  N 30° W, 136.19', 25" Elm, Spike &amp; Tag by PK (Old Wit.)  N 85° W, 48.56', 1/2" Re-rod (Alden's 1/4 Cor In east edge 28 Mile Road.  N 15° W, 73.96', 3/4" Pipe, Road P.I.</p>
---	--

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE 11-19-80  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655