

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

Nov 19 8 00 PM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE D. NEIDLANDER

For corners in
Calhoun County
(County)

Located In: _____ Corner Code ~~##~~ _____

1. Public Land Survey	T <u>1</u> S R <u>4</u> W	E-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald J. Davis, in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey by Gifford in 1889.
Tile found by Davis in 1976, 5/8" iron placed in tile.
SW corner house NE 28.60'
10" Oak N 40° E 15.00'
1" pipe North 76.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Tile destroyed by construction of sewerage tile field in 1980.
Found 5/8" iron by R. Carr as set from old surveys and witnesses.
Accepted this corner as local perpetuation of original corner.

LIBER 1716 PAGE 623

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" stainless steel rod with brass cap at corner. Set 5/8" re-bar beside.
Nail & tag 14" Burr Oak N 10° E 16.04'
SW corner of concrete block foundation N 30° E 29.48'
Nail & tag 8" Cherry N 20° W 46.00'
Nail & Tag 10" Elm S 10° W 38.68'
1" pipe North 76.02'



Signed by Donald J. Davis

Date November 4, 1993

Surveyor's Michigan License No. 17617