

SURVEY & REMONUMENTATION

1993

CALHOUN COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 19 1 00 PM '93

CLERK-REGISTRAR
 CALHOUN COUNTY, MICH.
 ANNE BLANCHARD

For corners in

Calhoun County
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>1</u> S R <u>4</u> W | <u>G-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald J. Davis, in a field survey on October 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey from parole evidence, by Gifford in 1889.

9" Hickory N 13° W 158 Links

24" Elm S 58° E 51 links.

R.R. Spike in paving over tile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike and 4" nail over tile.

Tile was 2' under road with rocks around.

Accepted this corner as perpetuation of original corner.

LIBER 1716 PAGE 619

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box at point.

Nail & tag 16" Oak N 80° E 29.60'

Nail & tag 20" Oak S 62° E 34.83'

Nail & Tag 12" Oak N 55° E 47.40'

2.5' West of centerline of 27 Mile Road.

137 feet North of centerline of North branch of Rice Creek.

Signed by _____ Date November 4, 1993

Surveyor's Michigan License No. 17617