

APPROVED

Date 11-12-96

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

19 NOV 96 1:57 P.M.

ANNE B. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 605

Register of Deeds Stamp & File Number

Form with fields for Calhoun (County), Located In, Corner Code, and numbered items 1-5 describing survey details.

Grid table with columns A-M and rows 2-13, containing numbers 1-36. A dot is marked in cell K-2.

Clarence Twp.

I, Donald J. Davis, in a field survey on October 25, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey in 1825 by Sibley. Resurvey in 1889 by Gifford, tile set. Consumer Power survey found 1-1/8" iron in 1967. South end of 48" CMP S 60° E 43.00' North end of 48" CMP N 60° E 48.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 48" CMP and used for resetting location. Excavated and found no evidence of iron or tile. Set tile corner location using the witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument 4" under surface of road. South end 48" culvert S60°E 43.00' North end 48" Culvert N 60° E 48.55' Nail & Tag 14" Elm N 10° W 24.00' Nail & Tag 14" Oak S 75° W 61.29' Nail & Tag 18" Maple S 75° E 65.50' Nail & Tag 8" Quad Maples N 80° W 52.32'



SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

Signed by Donald J. Davis, Surveyor's Michigan License No. 17617

Date November 25, 1996