

APPROVED

Date 11-12-96
CALHOUN COUNTY
REMONUMENTATION
For corners in
Calhoun

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 96 1:57 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 608

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
(County) Clarence Twp.		
1. Public Land Survey	T 1S R 4W	L-3
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Clarence Twp.

I, Donald J. Davis, in a field survey on October 16, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1825 by Sibley. Resurvey in 1889 by Gifford, tile set. Survey in 1967 by Consumers Power Co. Corner used was 6" I Beam in concrete.

SURVEY &
REMONUMENTATION

MAR 21 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 6" I beam in concrete and asked owner how long it was there. Dr James Kingsley said previous owner had removed tile and placed I beam in concrete at point.

Accepted the location for corner point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6" I Beam in concrete.

- Nail & Tag 26" Birch NW 2.30'
- Nail & Tag 38" Swamp Oak S 45° W 93.25'
- Nail & Tag 14" Swamp Oak West 42.29'
- Nail & Tag 14" Hickory S 75° W 83.74'
- Fence South and West



Signed by Donald J. Davis
Donald J. Davis
Surveyor's Michigan License No. 17617

Date October 25, 1996