

APPROVED

Date 11-17-96  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

19 NOV 96 1:58 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 609

Register of Deeds Stamp & File Number

Calhoun (County) Clarence Twp.	Located In:	Corner Code #
1. Public Land Survey	T 1 S R 4 W	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Clarence Twp.

I, Donald J. Davis, in a field survey on October 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey in 1825 by Sibley.
- Iron set by County Surveyor.
- Resurvey in 1889 by Gifford, tile set.
  - 10" Hickory N 54° E 54 links.
  - 10" Hickory S 48° E 55 links.
- 3/4" iron set by Consumers Power Co. in 1968.
  - 16" Hickory N 54° E 36.32'
  - Fence corner S 45° E 32.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Reset point from witnesses, excavated and found bricks and tile.
- Accepted as good perpetuation of original corner location.

**SURVEY &  
REMONUMENTATION**  
MAR 21 1997  
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Harrison monument 6" under surface of gravel road.
- Nail & Tag 24" Hickory N 54° E 36.52'
- Nail & Tag 10" Hickory S 55° W 28.58'
- Nail & Tag 12" White Oak S 35° W 43.24'
- Nail & Tag 14" Red Oak S 20° E 60.95'
- 19.5' North of fence East.
- 4' West of centerline of gravel road.



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date October 25, 1996