

APPROVED
 Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION.

**SURVEY &
 REMONUMENTATION**
 OCT 27 1994
 COMMISSION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in
 Calhoun
 (County)
 Located In: Corner Code ##
 Public Land Survey T 1 S R 5 W B-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 25 APR 94 12:18 P.M.
 ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

Donald J. Davis, in a field survey on April 9, 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

Description of original monument and accessories and/or subsequent restoration:
 Tile set in resurvey in 1891 by Gifford. Tile destroyed by road construction.
 Fences North and South. Found RR Spike set by DeKeyser from witnesses
 6" Butternut N 6° E 36 links. of 8" Maple (18" Maple) and in line with
 8" Maple S 2° W 41 links. fences North and South, 1973 and recorded
 in Liber 1027 on page 71.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found RR spike.
 Accepted as good perpetuation of original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Bernsten monument in monument box in line with fences North and South.
 Nail & Tag 18" Maple stump S 2° W 27.06'
 Nail & Tag 32" Maple S 50° E 41.49'
 Nail & Tag 28" Maple S 50° W 42.48'
 Nail & Tag 10" Cherry N 60° W 58.54'
 RR Rail Post 'North 30.81'

LIBER 1743 PAGE 586



signed by Donald J. Davis Date April 20, 1994
 Surveyor's Michigan License No. 17617