

Lee Top

APPROVED

CALHOUN COUNTY REMONUMENTATION

Date April 20, 1994
CALHOUN COUNTY
REMONUMENTATION.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Calhoun
(County)

Located In:

Corner Code #

1. Public Land Survey	T	1	S	R5	W	B-13
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Sec.	S		T		R	
	S		T		R	

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

3 JAN 95 10:19 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Donald J. Davis, in a field survey on April 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey of 1891 by Gifford 37.20 chains East of Township corner.
12" Hickory N 75½° W 171½ links. (GONE)
12" Hickory S 47½° E 136 links. (GONE)

Original Survey in 1825 by Sylvester Sibley.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found. Road cut destroyed corner. Ran Town line from southeast corner to southwest corner and set South ¼ Post at prorated distance.

CONVEY &
REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1783 PAGE 241

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument in gravel road.
Nail & tag 30" Oak N 5° W 25.30'
Nail & tag 18" Oak S 40° W 32.13'
Nail & Tag Utility pole South 29.40'
Nail & tag 24" Oak N 30° E 45.02'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date October 10, 1994