

# SURVEY & REMONUMENTATION

APR 26 1995  
CALHOUN COUNTY REMONUMENTATION

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

# APPROVED

Date 10-19-94  
**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in  
Calhoun

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>5 W</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

25 OCT 94 9:00 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

I, Donald J. Davis, in a field survey on August 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826.  
Resurvey in 1891 by Gifford (no tile set).  
Iron rod set by W. Crane in 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rod at intersection of fences.  
Power Pole North 23.40'  
Angle iron Post N 30° E 2.93'  
1.5' North of East and West fence.

Accepted as local surveyors point for corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument.  
Angle Iron post N 30° E 2.43'  
Wood fence post N 45° W 2.70'  
In line with fence to North.  
1.5' North of East and West fence.  
Corner is S 00°-04'-39" W 2651.92 feet from northwest corner.  
of Northwest ¼ is N 89°-20'-56" E.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		●	8		9		10		11		12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

LIBER 1773 PAGE 874



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date October 17, 1994