

1993

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

OCT 6 9 47 AM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NOBLANDER

For corners in
CALHOUN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 5 W C-11
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

STONE PLACED IN ORIGINAL SURVEY AND TILE SET BY GIFFORD IN 1891 RESURVEY.
12" SWAMP OAK S 75° E 56 LINKS.
12" SWAMP OAK S 38° E 42 LINKS.
OAK REMAINS FOUND BY J. KING IN 1973 AND CORNER RESET.

LIBER 1707 PAGE 276

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ALL EVIDENCE OF CORNER DESTROYED BY PIPELINE CONSTRUCTION. OBTAINED SECTION SURVEY BY DE KEYSER AND USED DISTANCES FROM SOUTH 1/4 AND EAST 1/4 POSTS TO REESTABLISH CORNER LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNISEN MONUMENT WITH BRASS CAP IN MONUMENT BOX IN PAVED ROAD.
NAIL & TAG 34" OAK N 60° W 70.78'.
NAIL & TAG 28" OAK S 80° W 161.06'.
NAIL & TAG 8" OAK S 20° E 86.08'.
UTILITY POLE N 20° W 193.26'.



Signed by Donald J. Davis

Date SEPTEMBER 24, 1993

Surveyor's Michigan License No. 17617