

SURVEY & REMONUMENTATION

APR 26 1995
CALHOUN COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED

Date 10-17-94
**CALHOUN COUNTY
REMONUMENTATION.**

<u>Calhoun</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>	
1. Public Land Survey	T <u>1 S</u> R <u>5 W</u>	<u>D-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 OCT 94 9:01 A.M.

Register of Deeds Stamp & File Number
CLERK - REGISTER OF DEEDS

I, Donald J. Davis, in a field survey on August 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826.
Resurvey in 1891 by Gifford, tile set.
12" Maple N 4° E 42 links.
8" Maple S 55° W 64 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron at location established by Wm. Crane and used in local surveys.
Accepted as good location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.
Nail & Tag utility pole N 5° W 48.75'
Nail & Tag 30" Maple N 60° E 49.41'
Nail & Tag utility pole S 30° E 60.61'
Nail & Tag 8" Ash S 60° W 59.60'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LIBER 1773 PAGE 878

Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date October 17, 1994

