

**SURVEY &
REMONUMENTATION**

APR 26 1995
CALHOUN COUNTY REMONUMENTATION

**COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED

Date 10-19-94
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

<u>Calhoun</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>5 W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 OCT 94 9:00 A.M.

Register of Deeds Stamp & File Number
ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald J. Davis, in a field survey on August 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826.
Resurvey in 1891 by Gifford. Tile set in stones.
Pipe placed in survey of Consumers parcel.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pinch top pipe in monument box. Dug and found rocks and tile under.
Accepted as good perpetuation of original corner.

LIBER 1773 PAGE 877

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.
Nail & Tag 12" Elm N 60° W 82.50'
Nail & Tag Utility pole S 45° E 66.60'
Nail & Tag 30" Maple S 40° E 32.70'
Nail & Tag 12" Locust N 70° W 129.70'



Signed by

Donald J. Davis
17617

Date October 17, 1994

Surveyor's Michigan License No. _____