

APPROVED

Date 11-12-96
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 FEB 97 3:47 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1916 PAGE 101

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code #
Lee Township		
1. Public Land Survey	T <u>1 S</u> R <u>5 W</u>	<u>E-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on November 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, Sylvester Sibley, 1826:
11" Tamarack...N31°W...22 links 5" D.O....S 64°W.....20 links

Resurvey, James Gifford, 1892:
Found stump of government bearing tree. Set stake. 8" Tamarack.....S33°E.....87 links

In April 1903, County Surveyor, P.A. Courtright, ran the line from the center to the West 1/4 Corner and set stakes every 10 chains along the line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated at intersection of fences South and East, found circle of stones around remnants of old fence post. Also, found traces of fence to North. Held old fence line intersection and stone pile as best location for West 1/4 Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Calhoun County Remonumentation Monument (Bermtsen Monument) at intersection of fences as described above.

Nail....N Side of 10" Oak.....East.....77.88'
Nail....NE Side of 6" Ash.....S68°E.....41.37'
Nail....NE Side of 6" Ash.....S54°E.....43.25'
Nail....E Side of 14" Ash.....S18°E.....46.25'

This is accepted as the best available evidence of the position of the original corner.

Signed by William K. Crane
William K. Crane, P.S.
Surveyor's Michigan License No. 29243

Date January 31, 1997

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

