

APPROVED

Date 11-12-96

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

19 FEB 97 3:47 P.M.

ANNE B. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 1916 PAGE 102

Register of Deeds Stamp & File Number

For corners in

Table with columns: Calhoun (County), Located In, Corner Code #. Includes entries for Lee Township, Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, William K. Crane, in a field survey on November 8, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column F and row 5.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, Sylvester Sibley, 1826:
7" R. Oak.....N31-1/2"E.....39 links
6" Boxwood.....S50-1/2"W.....14 links

Resurvey, James Gifford, 1892:
Measured West from Section corner to Meander Post. Set post at proportionate distance.
8" Hickory.....S59-1/2"E.....71 links
8" D.O.....S26"E.....75 links

Corner recorded by J.L. Wilcox, January 30, 1981, Liber 1243, Page 720:
20" Hickory.....S59-1/2"E.....46.86'
20" Hickory.....S26"E.....49.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron in monument box as described in Liber 1243, Page 720.
1.5' East of centerline of road South and 5.5' South of center of East and West road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" capped iron with Standard Calhoun County Remonumentation Monument (Berntsen Monument) in monument box.

Set Nail & spotter.....South side of 24" Walnut.....S84°W.....82.47'
Set Nail & spotter.....SW side of 14" Maple.....N22°W.....48.92'
Set Nail & spotter.....NW side of 30" Cherry.....N68°E.....60.44'
Set Nail & spotter.....South side of 26" Hickory.....S52°E.....46.93'

This is accepted as careful and faithful reestablishment of the position of the original corner.

Signed by William K. Crane, P.S.

Date January 31, 1997

Surveyor's Michigan License No. 29243

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

