

APPROVED

Date 11-12-96  
CALHOUN COUNTY  
REMONUMENTATION.  
For corners in

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

19 FEB 97 3:48 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1916 PAGE 105

Register of Deeds Stamp & File Number

Calhoun _____ (County)	Located In:	Corner Code #
Lee Township		
1. Public Land Survey	T <u>1</u> S <u>5</u> R <u>5</u> W	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on November 8, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, Sylvester Sibley, 1826:  
9" W. Oak....N74°W....21 links      10" Beech....N83°E....39 links

Resurvey, James Gifford, 1892:  
Found stake in road, drove at average distance. Set stake.  
18" W. Oak....S75-1/2°E....68 links      18" Cherry....N73°E....40 links

Gunn, 1927, found tile:  
24" Red Oak....S74°E....46.5'  
24" Red Oak....S42°E....48.8'  
12" Maple.....N54°W....39.2'  
3' South of line fence East

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile over tile with 1/2 flat iron driver beside it. 3' West of centerline, North and South road in line with fence East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron and first tile with Standard Calhoun County Remonumentation Monument (Berntsen Monument) over top of second tile. Placed monument box.

4" Oak.....S68°W.....29.18'  
4" Oak.....N56°W.....37.49'  
14" Cherry....N40°E.....57.04'  
14" Oak.....N78°E.....42.98'

This is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by William K. Crane  
William K. Crane, P.S.

Date January 31, 1997

Surveyor's Michigan License No. 29243