

APPROVED

Date 12-16-97 RRL
CALHOUN COUNTY
REMONUMENTATION.

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 DEC 97 2:38 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1985 PAGE 527

Register of Deeds Stamp & File Number

For corners in

| Located In: | Corner Code # |
|------------------------------------|-----------------------------|
| <u>CALHOUN</u> (County) | |
| LEE | |
| 1. Public Land Survey | T <u>1S</u> R <u>5W</u> L-9 |
| | T ___ R ___ |
| | T ___ R ___ |
| | T ___ R ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ |
| | S ___ T ___ R ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ |
| | S ___ T ___ R ___ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on DECEMBER 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1825, MULLET, DEPUTY SURVEYOR, SET STAKE, TAMARACK, 7", S15°E, 16 LINKS;
TAMARACK, 6", N74°W, 27 LINKS

1890'S, GIFFORD, SET TILE, STAKE NEAR FENCE EACH WAY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A HOLLOW FIRECLAY TILE INSIDE A 18" DRAIN TILE STOOD ON END. THE CORNER FALLS ON THE SOUTHEASTERLY SIDE OF A DITCH INTERSECTION. OLD FENCE RUNNING EAST AND SOUTH. ACCEPTED THIS CORNER AS A FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT WITH CARSONITE MARKER BESIDE. STAMPED SECTION INFORMATION AND LICENSE NUMBER IN BRASS CAP.

SOUTH, NAIL AND TAG IN WEST SIDE OF 10" BOX ELDER, 6.59'
S75°E, NAIL AND TAG IN SOUTHERLY SIDE OF 10" BOX ELDER, 40.13'
S50°W, NAIL AND TAG IN NORTHWESTERLY SIDE OF 10" BOX ELDER, 23.31'
S15°E, NAIL AND TAG IN SOUTHERLY SIDE OF 15" BOX ELDER, 36.09'
9' SOUTH OF DITCH RUNNING EAST AND WEST.



**SURVEY &
REMONUMENTATION**

Signed by [Signature] Date 12-16-97
Surveyor's Michigan License No. 39079 APR 07 1998