

APPROVED

Date 7-21-99 RRC

CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located in:	Corner Code #
CONVIS TOWNSHIP		
1. Public Land Survey	T <u>1S</u> R <u>6W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

27 JUL 1999 10:27:29 AM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2147** PAGE **714**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on JUNE 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY SYLVESTER SIBLEY D.S. IN 1826.
INTERSECTED WEST BOUNDARY 89 LINKS SOUTH OF POST
DONALD DAVIS P.S. NO. 17617, 1995 FOUND RAILROAD SPIKE

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RESURVEY TILES AT M-11 AND M-12 OF PENNFIELD TOWNSHIP.
SET STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN CASTING
ON LINE AT G.L.O. DISTANCE (58.74 FT) SOUTH FROM M-11 PENNFIELD TOWNSHIP.
RAIL ROAD SPIKE FOUND BY DAVIS IS 1.37 FT EASTERLY.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN CASTING:
48" OAK S 29°E 81.91' (NAIL AND SPOTTER)
UTILITY POLE N 78°W 61.22' (NAIL AND SPOTTER)
NORTHWESTERLY CORNER OF BRICK SIGN FOR CHURCH SOUTHWESTERLY 61.22'
24" SYCAMORE S 36°E 64.67 (NAIL AND SPOTTER)

THIS LOCATION IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]

Date 7-21-99

Surveyor's Michigan License No. 20704 ROBERT R. CARR