

APPROVED

Date 7-21-99 REC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u> (County)	Located in:	Corner Code #
CONVIS TOWNSHIP		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>31</u> T <u>1S</u> R <u>6W</u>	<u>A-12</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

27 JUL 1999 10:26:15 AM

ANNE R. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2147** PAGE **708**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on JUNE 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not ore than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT SET BY G.L.O.
CORNER SET BY ROBERT R. CARR P.S. 20704 AT MIDPOINT OF WEST LINE OF SEC 31 AFTER LOCATING RESURVEY TILE AT M-11, M-12, AND M-13 OF PENNFIELD TOWNSHIP AND ESTABLISHING A-11 CONVIS TOWNSHIP AT G.L.O. DISTANCE SOUTH OF M-11 PENNFIELD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ACCEPTED LOCATION OF CORNER AS ESTABLISHED ABOVE AND PLACED STANDARD CALHOUN COUNTY REMONUMENTANTION MONUMENT IN CASTING.

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN CASTING:
36" OAK N 07°W, 133.16' (NAIL AND SPOTTER)
UTILITY POLE N 66°W, 58.10' (NAIL AND SPOTTER)
38" OAK S 13°E, 120.04' (NAIL AND SPOTTER)
40" OAK S 12°E, 100.46' (NAIL AND SPOTTER)
CORNER M-12 OF PENNFIELD TOWNSHIP NORTHERLY 30.12'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date 7-21-99