

APPROVED

Date 7-21-99 RRC

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
CONVIS TOWNSHIP		
1. Public Land Survey	<u>T 1S R 6W</u>	<u>A-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

27 JUL 1999 10:25:49 AM

ANNE D. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 2147 PAGE 706

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on JUNE 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY SYLVESTER SIBLEY D.S. 1826 RESURVEY BY JAMES M. GIFFORD 1891, FOUND CORNER, LARGE STONE 36" BY 12" BY 10"

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON OVER RESURVEY TILE WITH ONE RESURVEY WITNESSES REMAINING (6" MAPLE S 35"E 42 LINKS) NOW A 40" MAPLE. REMOVED 1" IRON AND PLACED STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN CASTING OVER TILE.

SURVEY & REMONUMENTATION

MAR 13 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN CASTING
18" MAPLE S 28" W, 26.35' (NAIL AND SPOTTER)
40" MAPLE S 35" E, 27.56' (NAIL AND SPOTTER)
28" HICKORY N 13"E, 151.36' (NAIL AND SPOTTER)
S.E. CORNER GARAGE FOUNDATION N 69"W, 113.5'

THIS LOCATION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date 7-21-99