

APPROVED

Date 7-21-99 *RLC*

**CALHOUN COUNTY
REMONUMENTATION.**
For corners in

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>CALHOUN</u> (County) | Located in: | Corner Code # |
| CONVIS TOWNSHIP | | |
| 1. Public Land Survey | T <u>1S</u> R <u>6W</u> | <u>C-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

27 JUL 1999 10:26:51 AM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds, Stamps & File Number
LIBER 2147 PAGE 111

I, ROBERT R. CARR, in a field survey on JUNE 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY SYLVESTER SIBLEY D.S., 1826.
DONALD DAVIS P.S. NO. 17617, 1995 FOUND 1/2" IRON.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

**SURVEY &
REMONUMENTATION**

MAR 13 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PER DAVIS 1995.
IRON IS 1.3' NORTH OF CENTER LINE OF "N" DRIVE NORTH AND IN LINE WITH CENTERLINE OF 13 MILE ROAD.
FINDING NO OTHER RECORD OR EVIDENCE OF CORNER I ACCEPTED FOUND 1/2" IRON AND REPLACED WITH STANDARD CALHOUN COUNTY REMONUMENTATION MONUMENT IN CASTING.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN CASTING:
20" HICKORY N 25°E, 66.74' (NAIL AND SPOTTER)
12" MAPLE N 50°W, 56.35' (NAIL AND SPOTTER)
24" OAK N 20°W, 77.55' (NAIL AND SPOTTER)
14" CHERRY S 35°W, 103.95' (NAIL AND SPOTTER)

THIS LOCATION IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704

Date 7-21-99

ROBERT R. CARR