

MAR 30 1998

APPROVED

SECTION

Date 9-16-98 RRC
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

25 SEP 1998 2:27:35 PM

CALHOUN
(County)

Located In:

Corner Code #

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
LIBER **2062** PAGE **582**

- 1. Public Land Survey T 1S R 6W D-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3			⊙										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ROBERT R. CARR, in a field survey on SEPTEMBER, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 5 AND 8

A. Description of original monument and accessories and/or subsequent restoration:

SYVESTER SIBLEY D.S. 1826 SET ORIGINAL CORNER.

M.E. DEKEYSER R.L.S. #12019, 1971, SET 1/2" IRON AT PROPORTIONATE DISTANCE.

R.R. CARR P.S. #20704, AUGUST 1996, FOUND 1/2" IRON SET BY DEKEYSER ONE WITNESS REMAINING AND TOOK NEW WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PER CARR 1996 WITNESSES AND REPLACED WITH BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT WITH CARSONITE WITNESS POST ON NORTH SIDE.
RAILROAD TIE POST IN EAST-WEST FENCE, NORTH 5.5 FEET
10" WHITE OAK, S89°W 27.90 FEET, SET SPOTTER
18" WHITE OAK, N23°W 17.85 FEET, SET SPOTTER
14" WHITE OAK, N31°E 6.97 FEET, SET SPOTTER
12" WHITE OAK, S62°E 27.06 FEET, SET SPOTTER

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]

Date SEPTEMBER 16, 1998

Surveyor's Michigan License No. ROBERT R. CARR 20704